

Wildlife & Eco Guidelines

Did You Know?

YORhub has been working with the Yorkshire Wildlife Trust to...

develop some simple and low cost changes to construction projects that can reduce the impact on wildlife and help to enhance the environmental value of the built environment.



Lighting of construction site and compound

If lighting is to be used on site, lighting to be positioned to avoid light spill on hedgerows, trees and other biodiverse areas. If a bat roost is known to be in any building on site (such as old schools) then lighting should also be positioned to avoid these.

Lighting to be switched off when not in use. Where possible lighting to be avoided during night time hours onsite during the summer months.

Any lighting to be installed onsite in the final design of the project should also be positioned/ designed to avoid impacts on nocturnal species.

An editable version of these requirements that can be incorporated into your contracts can be [downloaded from our website](#)

www.yorhub.com

